



## Invert formwork Tunnel of Moutier

**Main contractor**

Groupement Tunnel de Moutier

**Sub-contractor**

Marti Technics Ltd.

**Drawn up**

2008

**Services provided by Marti Technics Ltd.**

Design, planning and performance of an invert formwork incl. construction.

**Technical data**

- Construction radius R = 5,100 m
- Formwork length 12.5 m
- Design complete hydrostatic pressure
- Formwork type single carriage
- Formwork weight 125 t
- Overall concrete length ca. 1,250 m
- Placing boom 2-way
- Projecture 7.5 m

